BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Constructionm of drains and improvements to roads in Chikkabettahalli in Attur, ward no:03 of Yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications Specification	cum	808.70	227.88	Rupees two hundredtwenty seven and paise eighty eight only
2	KSRB 2-1.1:Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manualluy (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled and after breaking of clods and neatly dressed as per specification Specification	cum	81.00	126.36	Rupees one hundred twenty six and paise thirty six only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14	Cum	195.53	4290.84	Rupees four thousand two hundred ninety and paise eighty four only
4	Providing and constructing granite.trap/basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high , bond stones at twom, apart in each course including cost of materials labour curing complee as per specification	cum	297.00	3484.22	Rupees three thousand four hundred eighty four and paise twenty two only
5	Providing ruled pointing of coursed stone masonry with cement motar 1:3 20 mm deep after raking joints to depth of 20mm necely lining including cost of materials, labour, HOM of machineries curing etc., complete as per specification and direction of the Engineer-in-charge	cum	660.00	78.44	Rupees seventy eight and paise forty four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
6	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal, coarse aggregate @0.878cum and fine aggregate @0..459 cummachine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	82.50	4779.00	Rupees four thousand seven hundred seventy nine only
7	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplaslesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapels, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2013-14	Cum	12.12	5639.76	Rupees five thousand six hundred thirty nine and paise seventy six only
8	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2013-14	Quintal	12.12	7380.72	Rupees seven thousand three hundred eighty and paise seventy two only
9	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.31/ PWD SR 2013-14	sqm	45.00	271.08	Rupees two hundred seventy one and paise eight only
10	KSRB 4.2.2:Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC Works laid in 15 cms, thick layers and well compacted vibrating,curing, finishing with necessary cement mortar, with all lead and lifts, etc.,complete (exclusive of cost of steel and fabrication charges)Ready mixed cement concrete M20 for raft foundation coloumn footing, main and secondary beams.(	cum	40.50	6464.88	Rupees six thousand four hundred sixty four and paise eighty eight only
11	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(	sqm	405.00	91.80	Rupees ninety one and paise eighty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
12	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement Item no 22.80 page No 191 SR 2013-14	Mtr	36.00	118.80	Rupees one hundred eighteen and paise eighty only
13	Providing and fixing 10 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcopacted cost of all materials labour curing comlete as per specification	sqm	660.00	1498.00	Rupees one thousand four hundred ninety eight only
14	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	sqm	808.70	94.82	Rupees ninety four and paise eighty two only

Technical Manager-2
KRIDL, BBMP
Bangalore - 560 001

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.